

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22321-00-02
Spot: CSWNW Sec/Twnshp/Rge: 7-31S-12W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: GRESS OWWO Well Number: 3
County: BARBER Total Vertical Depth: 4580 feet

Operator License No.: 5255
Op Name: MCGINNESS OIL COMPANY
Address: 1026 UNION CENTER BUILDING
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 255 WITH 165 SX CMT
Production: Size 5.5 feet: 4575 WITH 250 SX CMT
Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/28/2001 8:45 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC. 148-85
Proposal Rcvd. from: DOUGLAS H. MCGINNESS Company: MCGINNESS OIL COMPANY Phone: (316) 267-6065

Proposed Plugging Method: CIBP @ 3500' & 2 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/28/2001 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 3579-89', (3670-72 SQUEEZED), 3931-35', 4196-4222'. 8 5/8" WIPER PLUG NOT RUN. WELL WAS PRESSURED UP UNDER SWEDGE & VALVE SO DID NOT PULL SWEDGE & VALVE TO PUT IN PLUG CONTAINER. SET CIBP @ 3500' AND PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - & 100 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 550#.

INVOICED
DATE 4-5-01
INV. NO. 2001061577

RECEIVED
STATE CORPORATION COMMISSION
APR - 5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2217' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

APR 02 2001

Form CP-2/3