

To: 1 040935. 2-9
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,051-0000
SW SE SE, SEC. 9, T 31 S, R 12 W/E
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30931
Operator: Daystar Petroleum
Name & Address: 1321 W. 93rd North
Valley Center, KS 67147

Lease Name Elliott B Well #1
County Barber
Well Total Depth 4874 158.41 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 9 Month: 2 Year: 1995

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4486' w/125 sx cement; PBTD 4388'; Perfs at 4368-88'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 9 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 2-15-95

INV. NO. 42210

Signed Richard Lacey (TECHNICIAN)

RECEIVED
CORPORATION COMMISSION
FEB 13 1995
2-13-95
CONSERVATION DIVISION
WICHITA, KANSAS