

1 040372

12-5 15-007-21384.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D=21,186

SW SE SW, SEC. 12, T 31 S, R 12 W/EX

560 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name McMott "B" Well # 1

Operator: TXO Production Corporation

County Barber 142.87

Name & Address 1660 Lincoln Street, Suite 1800

Well Total Depth 4396 feet

Denver, CO 80264

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 3 p.m. Day: 5 Month: 12 Year: 19 89

Plugging proposal received from Bobby Swinehart

(company name) TXO Production Corporation (phone) 316-886-5605

were: 4 1/2" at 4002' PBD 3960' Perfs at 3376-78' & 3351-58' have been squeezed

Cement retainer set at 3370', Perfs at 3860-75'

1st plug sand back to 3750' and dump 4 sx cement on top of sand bridge with bailer,

2nd plug pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMM

DEC - 8 1989  
12-8-89

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 5 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 9/3/82-pumped 50 sx 50/50 Pozmix 2% gel, 2% cc down 4 1/2" & 8 5/8"

annulus. Displaced cement with one barrel of water.

12/4/89-Sanded back to 3750' and dumped 4 sx cement on top of sand bridge with bailer,

12/5/89 Top of cement in 4 1/2" & 8 5/8" annulus was tagged at 19'.

12/5/89 Top plug-Great Guns perforated 4 1/2" casing at 590', loaded 4 1/2" and took injection

rate at 2' BPM at 500#. Pumped down 4 1/2" casing with 100 sx cement. Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 2% gel by B.J. Titan. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I will / X observe this plugging.

DATE DEC 14 1989

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 26813

12-5