

1 040380

12-17

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,447A-00-01

C NW SE, SEC. 12, T 31 S, R 12 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Mott (ONWO) Well # 1

Operator: TXO Production Corporation

County Barber 151.78

Name & Address 1660 Lincoln Street, Suite 1800

Well Total Depth 4670 feet

Denver, CO 80264

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 19 Month: 12 Year: 1989

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4483' PBTD 4442' Perfs at 4285-95, 4266-76'

1st plug pump 1 sx hulls and 20 sx cement,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 19 Month: 12 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 950 psi and shut in 800 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If appropriate) observe this plugging.

INVOICED

Signed Stephen J. Zuber
(TECHNICIAN)

DATE 1-3-1990

INV. NO. 26872

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1989

CONSERVATION DIVISION
WICHITA, KANSAS