

To: **1040899**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-24 .75' S of  
E/2 W/2 NW, SEC. 13, T. 31 S, R. 12 W.

API NUMBER 15- 007-22,326 -00-01

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.  
Name & Address 110 N. Market, Ste. 205  
Wichita, KS 67202

3885 feet from S section line

4290 feet from E section line

Lease Name Mott A Well # 1

County Barber

Well Total Depth 4370 142.02 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 24 Month: 10 Year: 1994

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

logs: 4 1/2" at 4368' w/325 sx cement, BP @ 4235', Perfs at 3362-56, 4272-76, 4280-86'

1st plug set CIBP at 3322' and dump 4 sx cement on top of CIBP through dump bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 24 Month: 10 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3322' and dumped 4 sx cement on top of CIBP through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 950 psi and shut in 600 psi.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2650' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
observe this plugging.

DATE 11-7-94

INV. NO. 41593

Signed Stephen J. Pfeifer  
(TECHNICIAN)