

To: 1 041218  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-22,348 ~~00-00~~  
E/2 NW NW, SEC. 13, T 31 S, R 12 W/E

11-5

4620 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 31191  
Operator: R & B Oil & Gas Inc.  
Name & Address: 904 N. Logan  
Attica, KS 67009

Lease Name Mott # Well # 2-A  
County Barber 141.27  
Well Total Depth 4347 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Shawnee Well Service License Number 30346  
Address Attica, KS 67009

Company to plug at: Hour: 8:30 a.m. Day: 5 Month: 11 Year: 19 96

Plugging proposal received from Randy Newberry  
(company name) R & B Oil & Gas Inc. (phone) 316-254-7972

Work: 4 1/2" at 3552' w/150 sx cement, PBTD 3509', Perfs at 3372-81'  
1st plug set CIBP at 3300' and dump 2 sx cement on top,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Bill Johnson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:15 a.m. Day: 5 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3300' and dumped 2 sx cement on top,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOLCED  
observe this plugging.

DATE NOV 14 1996  
46968

Signed Stephen J. Puffer  
(TECHNICIAN)

154545  
1996 NOV 13 4 11:55 PM  
TECHNICIAN