

To: 1 031236 : 7-23  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22,367-0000  
NW NE SW, SEC. 13, T. 31 S, R. 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123  
Operator: Pickrell Drilling Company, Inc.  
Name:  
Address 110 N. Market, Ste. 205  
Wichita, KS 67202

2310 feet from S section line  
3630 feet from E section line  
Lease Name Reeves "E" Well # 1  
County Barber 14/21  
Well Total Depth 4345 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 23 Month: 7 Year: 1993

Plugging proposal received from Don Aumiller  
(company name) Pickrell Drilling Co., Inc. (phone) 316-532-3511

were: 4 1/2" at 3520' w/150 sx cement, PBSD 3489', Perfs at 3346-51'  
1st plug set CIBP at 3305' and dump 2 sx cement on top,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 23 Month: 7 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3305' with 2 sx cement on top,  
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 100 sx cement.  
Maximum pressure 800 psi and shut in 250 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2650' of 4 1/2" casing.  
If additional description is necessary, use BACK of this form.

INVOICED  
DATE 7-28-93  
INV. NO. 38217

Signed Steve Skurmont  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

JUL 27 1993