

To: 1 040774
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-12

API NUMBER 15- 007-21,817-6000
SW NE SE, SEC. 35, T 31 S, R 12 W/EX
1650 feet from S section line
990 feet from E section line
Lease Name Lawrence Well # 1
County Barber
Well Total Depth 4404 43.13 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428
Operator: Graves Drilling Company
Name & Address P.O. Box 8250
Wichita, KS 67208

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 383

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1 p.m. Day: 12 Month: 8 Year: 19 93

Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4400' w/125 sx cement. Perfs at 4332-4339'
1st plug sand back to 4280' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 12 Month: 8 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1150 psi and shut in 1050 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing. STATE CORPORATION COMMISSION
Additional description is necessary, use BACK of this form.

INVOICED

DATE 8-24-93
INV. NO. 38400

Signed Stephan J. [Signature] CONSERVATION DIVISION
(TECHNICIAN) Wichita, Kansas

8-18-93
RECEIVED
AUG 18 1993