

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21205-00-00  
Spot: NWSENE SW Sec/Twnshp/Rge: 36-14S-32W  
1775 feet from S Section Line, 2025 feet from W Section Line  
Lease Name: KREBS E Well #: 1  
County: LOGAN Total Vertical Depth: 4373 feet

Operator License No.: 34639  
Op Name: BLACK TEA OIL, LLC  
Address: 1014 E. 29TH ST.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4360		190 SX
SURF	8.625	268		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2015 9:00 AM  
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.  
Proposal Rcvd. from: COLE DINKEL Company: BLACK TEA OIL, LLC Phone: (785) 445-3816

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls, 11 sx gel. Perforations: 4032' - 4042'. Port Collar at 2120' w/400 sx cement.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/01/2015 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4003' and pumped 11 sx gel followed by 80 sx cement w/300 # hulls. Pulled tubing to 2210' and pumped 110 sx cement. Pulled tubing to 1105' and pumped 140 sx cement. Pulled tubing out and topped off casing w/15 sx cement. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 300 psi.

GPS: 38.79115 -100.82928

Perfs:

Top	Bot	Thru	Comments
4032	4042		

Remarks: GLOBAL CEMENT TICKET # 1666

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

MAY 11 2015

RECEIVED