

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-06755-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 31-14S-13W  
4975 feet from S Section Line, 4318 feet from E Section Line  
Lease Name: L MILLER Well #: 1A  
County: RUSSELL Total Vertical Depth: 2949 feet

Operator License No.: 34912  
Op Name: C12 KANSAS OIL, LLC  
Address: 1900 WAZEE ST. SUITE 200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	2846		50 SX
SURF	15.5	60		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2015 12:00 AM  
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: AVEN WEAVERLING Company: C 12 KANSAS OIL INC. Phone: (785) 623-3221

Proposed Plugging Method: 04/28/15- Ordered 150 sx 60/40 pozmix 4% gel cement.  
04/29/15- Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
Casing reports showed 60' of 15 1/2" left in hole, 349' of 12 1/2" pulled, 654' 10" pulled, 2275' 8 5/8" pulled, 2875' 6 5/8" cemented in with 50 sx cement.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/01/2015 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/29/2015- Ran tubing to 2910' and pumped 150 sx cement. Displaced 6 bbl and POOH. Shut down.  
04/30/2015- Ran in with wireline and tagged cement at 2450'. Perforations at 1350', 650' and 340'. Ran tubing to 2431' and pumped 5 sx gel followed by 80 sx cement w/200 # hulls. Pulled tubing to 1364' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 660' and pumped 125 sx cement w/100 # hulls. Circulated cement to pit. POOH. Hooked to braden head and pressured up to 150 psi. Filled casing with 20 sx cement to top off.  
05/01/2015- Checked fill up. Cement dropped 120'. Topped off with 15 - 20 sx cement.  
GPS: 38.79752 -098.81465

Perfs:

Top	Bot	Thru	Comments
2846	2949		
2227	2233		

Remarks: QUALITY CEMENTING TICKET #S 11262 AND 1810

Plugged through: TBG

5/13/15 CPM

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

KCC WICHITA

CM

MAY 11 2015

RECEIVED

Form CP-2/3