

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-26094-00-00  
Spot: N2SENESE Sec/Twnshp/Rge: 14-20S-11W  
1956 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ZAHORSKY M Well #: 1  
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 4184  
Op Name: CASINO PETROLEUM, LLC  
Address: PO BOX 415  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	277		255 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2015 12:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Revd. from: LARRY Company: SOUTHWIND DRILLING, INC. Phone: (650) 617-3478

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE  
Date/Time Plugging Completed: 04/29/2015 8:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @1421 w/50 sx  
2nd plug @640 w/100 sx  
3rd plug @327 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx


Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

5/13/15 CRM

MAY 01 2015

KCC WICHITA

Form CP-2/3

MAY 11 2015

RECEIVED