

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20324-00-00
Spot: SESESENW Sec/Twnshp/Rge: 26-22S-40W
2610 feet from N Section Line, 2610 feet from W Section Line
Lease Name: HOWELL Well #: 1-26
County: HAMILTON Total Vertical Depth: 2750 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2750	0	WITH 550 SX CMT
SURF	8.625	379		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/01/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT WITH 200# HULLS. DISPLACE TO 1100'. RUN CBP TO DETERMINE TOC. PERFORATE AND/OR TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2015 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1300'. PRESSURE TEST CASING TO 500#. HOLDING. RUN CBL FROM 1100' TO 0'. TOP OF CMT BEHIND THE 4 1/2" CASING IS 60'. RUN TBG TO 1109' & CIRCULATE CMT TO SURFACE WITH 70 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 250PSI.

Perfs:

Top	Bot	Thru	Comments
2712	2722		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

5/13/15 CKM

District: 01

Signed Ken Jehlik
(TECHNICIAN)

KCC WICHITA JA

MAY 11 2015

RECEIVED

RECEIVED
MAY - 7 2015
KCC DODGE CITY