

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20729-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 6-22S-40W  
1254 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: GOULD A Well #: 3-6  
County: HAMILTON Total Vertical Depth: 2829 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2702		
PROD	4.5	2829	0	WITH 650 SX CMT
SURF	8.625	845		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/29/2015 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/29/2015 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2702'. RUN TBG TO 2352' & SPOT 25 SX CMT WITH 150# HULLS. FULL CIRCULATION. PULL TBG TO 1200' & CIRCULATE CMT TO SURFACE WITH 80 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT. PUMP 35 SX CMT DOWN THE ANNULUS TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2732	2742		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

KCC WICHITA

MAY 11 2015

RECEIVED

5/13/15 clem

RECEIVED  
MAY - 1 2015  
KCC DODGE CITY

*MP*