

1 040793

10-14

API NUMBER 15- 007-21,622 -0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW, SEC. 35, T 31 S, R 12 W/X
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428

Lease Name Benifield Well # 1

Operator: Graves Drilling

County Barber 145.34

Name & Address 8100 E. 22nd St.

Well Total Depth 4472 feet

P.O. Box 8250

Conductor Pipe: Size feet

Wichita, KS 67208

Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9 a.m. Day: 14 Month: 10 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4470', with 125 sx cement, CIBP 3840', Perfs at 3752-56'

1st plug sand back to 50' above perfs with 5 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 a.m. Day: 14 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 5 1/2" casing.

OCT 18 1993

(If additional description is necessary, use BACK of this report.)

INVOICED (did / observe this plugging.)

CONSERVATION DIVISION Wichita, Kansas

DATE 10-28-93

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 39065