

2040245

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- old well

SE 1/4 SW 1/4 SEC. 3, T. 30 S., R. 7 W. 10

2970 feet from N/S section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Bliss Well # 2

Operator Name & Address Pickrell Drlg Co.

County Kingman 137.15

110 N. Market #205

Well Total Depth 4220 feet

Wichita Ks.

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8⁵/₈ feet 204

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corp. License Number _____

Address Medicine Lodge Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Elmo

(company name) Clark Corp (phone) _____

were: _____

FBTD 4174 Sand to 4070, 3 Hull, 15 gel, 100 sx

4¹/₂. 4216

Perf. 4122-4132

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1200 Day: 24 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT Clark Corporation moved over the hole,

and dumped sand into the 4¹/₂" casing to cover the

perforations, T.O.S. 4070'. The 4¹/₂" casing was shot off

and recovered from 3700'. The top was squeezed-plugged

than the 8⁵/₈" surface casing, by pumping 3 sacks of Hulls, 15

sacks of gel, and 80 sacks of cement, a wear plug and 20 sacks

Remarks: of cement. Allied Cementing #2149 MX STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

RECEIVED
JAN 30 1986

IN VOICED

(If you do not) observe this plugging.

DATE JAN 31 1986

Signed Steve C... CONSERVATION DIVISION
(TECHNICIAN) 20

INV. NO. 12219