

15-095-01099-0000

2-070377 141

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: _____

_____ NW, SECTION 3 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 5123

4950 FEET FROM S SECTION LINE

4950 FEET FROM E SECTION LINE

OPERATOR Pickrell Drilling Co., Inc

NAME & 110 N. Market, #205

ADDRESS Wichita, KS 67202

LEASE NAME: Bliss #4

COUNTY: Kingman 137.31

WELL TOTAL DEPTH: 4225' P/B 4191

CONDUCTOR PIPE: _____ " @ _____'

SURFACE CASING: 8-5/8" @ 217'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clark Well Service

ADDRESS: Box 187, Medicine Lodge, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 4 MONTH: 6 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Don Aumiller

COMPANY NAME: Pickrell PHONE: 262-8427

WERE: Sand bottom to 4050' & 4 sx - 35 sx @ 1267' - 35 sx @ 803' - 270' to surface

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 11:30 DAY: 4 MONTH: 6 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded bottom to 4050' and 4' sx common - shot 4-1/2" csg off @ 3555' - pulled all csg - ran tub in to 1267' - pumped 35 sx - pulled to 803' - pumped 35 sx - pulled to 270' - circ to surface.

REMARKS: Allied #1307 60/40 4%

I DID OBSERVE THIS PLUGGING.

JUN 07 1991 06-07-91

INVOICED

Wichita, Kansas
DATE 6-24-91

Jack Luthi
Jack Luthi (AGENT)

INV. NO. 32228