

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01098-00-00  
Spot: SENENW Sec/Twnshp/Rge: 3-30S-7W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: BLISS Well Number: 3  
County: KINGMAN Total Vertical Depth: 4225 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 SOUTH MAIN - SUITE 505  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 219 155 SX CMT  
Production: Size 4.5 feet: 4225 125 SX CMT \$137.31  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/12/2001 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: RON SMITH Company: CLARKE CORP Phone: (316) 886-5665

Proposed Plugging Method: Sand to 4083 and 4sxs. 35sxs-1100'. 35sxs-700'. 270'-0'.

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/12/2001 9:00 AM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 4083 and 4sxs of common shot 4 1/2" casing off at 3300'. Pulled casing ran tubing to 400'. Pumped 35sxs pulled to 700'. Pumped 35sxs, pulled to 270'. Pumped cement to surface.

INVOICED  
DATE 7-3-01  
INV. NO. 2002060001

RECEIVED  
KCC DISTRICT #2  
JUN 19 2001  
WICHITA, KS

Remarks: ALLIED # 7760 60/40 4%GEL

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)