

3-29

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
4-14-94
APR 14 1994

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: N/A
C SE NE, SECTION 2 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 6236 3300 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR MTM PETRO INC
NAME & P O BOX 82
ADDRESS SPIVEY KS 67142

LEASE NAME: POUND #2
COUNTY: KINGMAN

WELL TOTAL DEPTH: 4130' 134.22

PIPE: _____

SURFACE CASING: 8-5/8" @ 320'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS
COMPANY NAME: SHAWNEE WELL SERVICE PHONE: _____

WERE: 5-1/2" @ 4126' - OH 4126'-30' - SAND BACK TO 4075' &
5 SX - RECOVER PIPE - 35 SX @ 1050' - 35 SX @ 700' -
CIRC 370' TO SURF

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: _____ DAY: 29 MONTH: 3 YEAR: 1994

ACTUAL PLUGGING REPORT:
OPEN HOLE WAS FILLED W/SAND FROM 4130' TO 4075' &
CAPPED W/5 SX CMT - 5-1/2" RECOVERED FROM 2701' &
PULLED TO 1063.63 WHERE 35 SX CMT SPOTTED - 5-1/2"
PULLED TO 700.90 & 35 SX PLUG PLACED - 5-1/2" PULLED TO
350' & CMT CIRC TO SURF - REMAINING PIPE PULLED FROM
WELLBORE & CMT TOPPED OFF

REMARKS: ALLIED CMT #6305 - 60/40 4% GEL

INVOICED
I DID OBSERVE THIS PLUGGING.

[Signature]
STEVE VAN GIESON (AGENT)

DATE 4-18-94
INV. NO. 40296-1
3-29