

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-4

API NUMBER: 15-095-21,461-2000

C SE SW, SECTION 14 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 6344 660 FEET FROM S SECTION LINE
OPERATOR ENERGY OIL & GAS INC 3300 FEET FROM E SECTION LINE
NAME & P.O. BOX 121
ADDRESS RAGO, KS 67128

LEASE NAME: DUNKELBERGER-HOPPER #1 137.15
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4220' PB 4154'
PIPE: 5 1/2" @ 4218'
SURFACE CASING: 8 5/8" @ 246'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: D S & W WELL SERVICE
ADDRESS: BOX 231 CLAFLIN, KS 67525 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 4 MONTH: 10 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: KENT
COMPANY NAME: D S & W WELL SERVICE PHONE: (316) 587-3361
WERE: SAND TO 4050' - 5 SACKS
35 SACKS AT 1200'
35 SACKS AT 800'
300-0'

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 16 1996

PLUGGING PROPOSAL RECEIVED BY: J.L. CONSERVATION DIVISION WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 4:30PM DAY: 4 MONTH: 10 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 4050' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 2985'. PULLED TO 1200'. PUMPED 35 SACKS OF CEMENT. PULLED TO 800'. PUMPED 35 SACKS. PULLED TO 300', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL HALLIBURTON #338462

INVOICED

DATE OCT 17 1996

INV. NO. 46702

I DID OBSERVE THIS PLUGGING.

Jack L. Luthi
JACK L. LUTHI