

9-15

2-030066

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-095-20,082-0000

C SE NE, SECTION 12 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 31378 3300 FEET FROM S SECTION LINE

OPERATOR UNIVERSAL RESOURCES CORPORATION 660 FEET FROM E SECTION LINE

NAME & 44 SE 20 ROAD

ADDRESS GREAT BEND, KS 67530

LEASE NAME: MESSENGER Q2

COUNTY: KINGMAN

WELL TOTAL DEPTH: 4099' 133.22

PIPE: 5 1/5" @ 4099'

SURFACE CASING: 8 5/8" @ 235'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: P.O. BOX 467, CHASE KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 15 MONTH: 9 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: TERRY NAYLOR

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: PLUG AT 1100' WITH 35 SACKS, 750' WITH 35 SACKS, 300' TO SURFACE WITH CEMENT. SAND UP OVER PERF AND PLACE 5 SACK PLUG.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 6:15 DAY: 15 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED UP OVER PERFS AT 4016', ADD 5 SACK PLUG. PULLED 5 1/2" CASING, RECOVERED 3009'. SECOND PLUG AT 1100' WITH 35 SACKS. 60/40 POZ MIX THRU 5 1/2". THIRD PLUG AT 780' WITH 35 SACKS, THRU 5 12", POZ MIX. FOURTH PLUG CEMENTED FROM 332' TO SURFACE THRU 5 1/2".

START 4:15, FINISH 6:15 CASING BEING PULLED WHEN I ARRIVED

ARRIVED AT LOCATION: 1300 HRS CEMENTED AT 15:00 HRS

REMARKS: ALLIED CEMENTING CO. #5743 PATTON TANK TRUCK FOR WATER

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

SEP 17 1997

Bill Johnson
BILL JOHNSON

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3

REV. 3/90

INVOICED

DATE 9-24-97

INV. NO. 49094

de