

15-095-20121-0000
6-21
15-095-20121-00-00

2 100502

API NUMBER 15- 10-15-68

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION
STATE CORPORATION COMMISSION
NW NW SE, SEC. 12, T 30 S, R 7 W/EX
feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT **JUL 13 1989**

Operator License # 5238 CONSERVATION DIVISION Wichita, Kansas Lease Name Cessna Twin Well # C-1
Operator: Petroleum, Inc. County Kingman 133.48
Name & Address 301 N. Main, #900 Well Total Depth 4107 feet
Wichita, KS 67202 Conductor Pipe: Size 5-1/2 feet 4105
316-291-8282 Surface Casing: Size 8-5/8 feet 251

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated perf 4085'-4095'

Plugging Contractor Hays Well Service License Number 5429

Address Attica KS

Company to plug at: Hour: 9:45 Day: 21 Month: 6 Year: 19 89

Plugging proposal received from Terry Naylor

(company name) B. J. Titan (phone) 316-793-8471

were: Pump bottom CIBP 4065' - circ thru tubing inside 5-1/2" - squeeze holes in casing (748-1802) with 250 sx 60/40 & 100 sx common up to 800# PSI - packer place at 810' - new T.D. 825' - circ thru tubing gel from 825' to 300' - circ cement from 300' to surface.

Plugging Proposal Received by J. L. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00p Day: 21 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT CIBP at 4065' & 2 sx cement - squeezed thru tubing (packer set at 810') 250 sx 60/40 & 100 sx common into casing from 825' to 3900' with 800# PSI - new T.D. 825' - circ thru tubing 13 bbls 9# gel from 825' to 300' - pulled tubing to 300' - circ 85 sx cement inside and outside 5-1/2" to surface.

Remarks: B.J. Titan #513166 60/40 4% gel - May 1988 Howco #415935

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-18-89

Signed J. L. Sanders (TECHNICIAN)

INV. NO. 25366 UK