

040765

2-040765

5-16

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

JUN 27 1994

CONSERVATION DIVISION
WICHITA, KS

15-095-00169-00-01

API NUMBER: 8/22/56 D-05,275

SW SW NW, SECTION 10 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 6581

29.70
49.50
FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

OPERATOR BISON ENERGY CORP
NAME & 8329 E CENTRAL
ADDRESS WICHITA KS 67206

LEASE NAME: WELCH #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4202' 136.56

PIPE:
SURFACE CASING: 8-5/8" @ 200'

ABANDONED OIL WELL X GAS WELL INPUT WELL SLD X D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: STEVE ANDERSON
COMPANY NAME: BISON ENERGY PHONE:

WERE: SAND TO & 5 SX - SHOT 1230' TO 1260' - 35 SX
@ 1200' - 35 SX @ 800' - CIRC 250' TO SURF

PLUGGING PROPOSAL RECEIVED BY:


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 16:30 DAY: 16 MONTH: 5 YEAR: 1994

ACTUAL PLUGGING REPORT:
PERFS WERE COVERED TO 3702' & CAPPED W/5 SX CMT - PIPE
SHOT LOOSE @ 1263' & PULLED TO 1206' & 35 SX CMT
SPOTTED - PIPE WAS PULLED TO 668' & 35 SX CMT SPOTTED
- PIPE PULLED TO 275' & CMT CIRC TO SURF

REMARKS: ALLIED 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.


STEVE VAN GIESON (AGENT)

INVOICED
JUN 28 1994

DATE
INV. NO. 40671
5-16

FORM CP-2/3
REV. 3/90

DW