

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21278-00-00  
Spot: CE2SENE Sec/Twnshp/Rge: 9-30S-7W  
1980 feet from N Section Line, 330 feet from E Section Line  
Lease/Unit Name: RAGO JUNCTION Well Number: 1  
County: KINGMAN Total Vertical Depth: 4200 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S. MAIN ST.  
KINGMAN, KS 67068

Conductor Pipe: Size feet: 8136.50  
Surface Casing: Size 8.625 feet: 265 175 SX CMT  
Production: Size 4.5 feet: 4197 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/02/2002 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Perfs 4122'-30'. 35sxs-1250', 35sxs-730'. Sand to 4052'- and 4sxs. Circulated 310'. Rec 3220'

Plugging Proposal Received By: STEVE VANGIESON  
Date/Time Plugging Completed: 08/02/2002 2:00 PM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were covered w/sand from 4156' to 4052' and capped w/4sxs of cement. The casing was recovered from 3220' and pulled to 1250' where 35sxs of cement was spotted. Pulled casing to 730' spotted 35sxs cement. Pulled casing to 310' and circulated cement to surface. Pulled remaining casing and topped off cement.

RECEIVED  
KCC DISTRICT #2

AUG 02 2002


WICHITA, KS

Remarks: ALLIED CEMENT # 8675 60/40 POZ., 4% GEL.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 8-5-02

NO. 2003060162