

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20533-00-00
Spot: CW2NWSW Sec/Twnshp/Rge: 8-30S-7W
1980 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: KOHMAN Well Number: 1
County: KINGMAN Total Vertical Depth: 4545 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 7802
WICHITA, KS 67278

Production Casing Size: 4.5 feet: 4247 200 SX CMT
Surface Casing Size: 8.625 feet: 232 200 SX CMT

\$ 147.71

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/11/2003 10:30 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DARYL HANSON Company: MCCOY PETRO.CORP. Phone: (620) 272-1296

Proposed Plugging Method: AS KCC REQUIRES.

RECEIVED
KCC DISTRICT #2

APR 22 2003

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON
Date/Time Plugging Completed: 04/11/2003 10:30 AM

WitnessType: Plugging Operations Partially Witnessed
KCC Agent: STEVE VANGIESON

Actual Plugging Report:


THE PERFS WERE COVERED WITH SAND TO 3725' AND CAPPED WITH 4 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 2715', AND PULLED TO 1150', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 300', WHERE CEMENT WAS CIRCULATED TO SURFACE.

Remarks: ACID SERVICES. 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

4-22-03

INV. NO.

2003061448