

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21188-00-01
Spot: E2NWNW Sec/Twnshp/Rge: 8-30S-7W
4620 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: KOHMAN Well Number: 5-8
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 7802
WICHITA, KS 67278

Production Casing Size: 5.5 feet: 4776
Surface Casing Size: 8.625 feet: 297

RECEIVED
KCC DISTRICT #2
813813
MAR 5 2003

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 12/05/2001 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

AS REQUIRE BY KCC

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/07/2001 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4100' AND CAPPED WITH 4 SKS OF CEMENT. THE CASING WAS SHOT AT 3010' AND CAME LOOSE AT 2833'. THE CASING WAS PULLED TO 1250', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 331', WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING CASING WAS PULLED.

Remarks: ACID SERVICES 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3-6-03

INV. NO. 2003061270