

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21425-00-00  
Spot: CSWSENW Sec/Twnshp/Rge: 8-30S-7W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: KOHMAN Well Number: 7  
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 7802  
WICHITA, KS 67278

Production Casing Size: 5.5 feet: 4248 175 SX CMT  
Surface Casing Size: 8.625 feet: 265 200 SX CMT

\$138.13

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/15/2003 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DARYL HANSON Company: MCCOY PETRO. CORP. Phone: (620) 272-1296

Proposed  
Plugging  
Method:

AS KCC REQUIRES.

RECEIVED  
KCC DISTRICT #2  
APR 22 2003  
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON  
Date/Time Plugging Completed: 04/15/2003 10:30 AM

Witness Type: Plugging Operations Partially Witnessed  
KCC Agent: STEVE VANGIESON


**Actual Plugging Report:**

THE PERFS WERE COVERED WITH SAND TO 3570', AND CAPPED WITH 5 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 3015' AND PULLED TO 1150', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 300', WHERE CEMENT WAS CIRCULATED TO SURFACE.

Remarks: ACID SERVICES 60/40 4% GEL

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

INVOICED

DATE 4-22-03

INV. NO. 2003061448