

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21456-00-00  
Spot: CNENWSW Sec/Twnshp/Rge: 8-30S-7W  
2310 feet from S Section Line, 990 feet from W Section Line  
Lease/Unit Name: KOHMAN Well Number: 8  
County: KINGMAN Total Vertical Depth: 4200 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 78020  
WICHITA, KS 67278

Conductor Pipe: Size feet: 36.50  
Surface Casing: Size 8.625 feet: 265 200 SX CMT  
Production: Size 5.5 feet: 4195 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/16/2002 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICES Phone:

Proposed  
Plugging  
Method:

Perf 3772'-3775 and 4090'-4108'. Sand to 3720' and 5sxs. 35sxs-1300', 35sxs-700', and circulate 300'.

Plugging Proposal Received By: STEVE VANGIESON  
Date/Time Plugging Completed: 07/16/2002 11:00 AM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perms were sanded from 4148'-3729' and capped w/5sxs cement. The 5 1/2" was recovered from 3025' and pulled to 1300' where 35sxs of cement was spotted. The pipe was pulled to 700' where 35sxs of cement was spotted. The pipe was pulled to 300' where cement was circulated to surface the remaining pipe was pulled and cement topped off.

RECEIVED  
KCC DISTRICT #2

JUL 24 2002


WICHITA, KS

Remarks: ACID SERVICES 60/40, 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE: 7-25-02

INV. NO. 200360090