

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20,766-0000

LEASE NAME WATSON "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2543 Ft. from S Section Line

3960 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 35 TWP. 34S RGE. 42 ~~XXX~~ (W)

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

COUNTY Morton

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 2-6-85

Character of Well D&A

Plugging Commenced 12-29-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-1-90

The plugging proposal was approved on 11/3/89 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No. Logs on file w/ACO-1.

Producing Formation St. Louis Depth to Top 4700 Bottom 4906 T.D. 4906

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
St. Louis	D&A	4700	4906	5 1/2	4700	2836

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1). Loaded hole w/100 bbl mud 2). Set CIBP @ 4600 w/2 sxs common cmt on top. 3). Shot off casing @ 2836 4). Spotted 30 sxs common cmt from 2800-2700 5). Spotted 50 sxs cmt from 1416-1216 6). Spotted 35 sxs common from 700-600 7). Spotted 10 sxs common from 40-0 8). Recovered 2836' 5 1/2, 15.5# csg 9). Cut off wellhead 3' below GI, and welded in cap.
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Sargent's Casing Pullers Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

M. L. Pease - Division Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JAN 30 1990 (Signature) M. L. Pease

M. L. Pease - Division Production Manager
(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN to before me this 26 day of January, 1990

Cheryl Steers

Notary Public

My Commission Expires



10). Restored location. 11). Witnessed by Glenn Barlow with the Kansas Corporation Commission.

