

15-129-10547-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 4-30-56

LEASE NAME Taloga Morrow "G"

WELL NUMBER 302

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 42 ~~XX~~ or (W)

COUNTY Morton

Date Well Completed 5-10-56

Plugging Commenced 9-9-91

Plugging Completed 9-11-91

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-3051

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-8-91 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? _____

Producing Formation Morrow "G" Depth to Top 4514 Bottom 4556 T.D. 4650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1530	0
				4 1/2	4621	2030

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. TIH w/1-1/4" tbg to 4500'. Ld hole w/9 ppg DM, pmpd 1 sx hull & 20 sxs cmt from 4500'-4300'. TOH w/1-1/4" tbg to 4300' & circ. TOH W/1-1/4" tbg, shot 4-1/2" csg off @ 2030 (freepoint). Pmpd 30 sxs cmt from 2030'-1930'. pmpd 40 sxs cmt from 1570'-1470'. pmpd 30 sxs cmt from 650'-550'. Pmpd 10 sxs cmt from 40'-3'. Rec 66 its 4-1/2" csg. Cut off & capped 8-5/8" csg 3' below GL.

(If additional description is necessary, use BACK of this form.) KCC Rep - Glenn Barlow

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed with the Kansas Corporation Commission, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

OCT 16 1991

CONSERVATION DIVISION
WICHITA, KS

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 91

My Commission Expires:



Cheryl Steers
Notary Public