

API NUMBER 15-119-20,950-0000

LEASE NAME Angell Unit

WELL NUMBER 6

960 Ft. from S Section Line

1680 Ft. from ~~S~~ Section Line

SEC. 6 TWP. 33S RGE. 29 ~~W~~ W

COUNTY Meade

Date Well Completed 10/31/95

Plugging Commenced 9/15/98

Plugging Completed 9/17/98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Samedan Oil Corporation

ADDRESS 9400 N. Broadway, Suite 700  
 Oklahoma City, Oklahoma 73114

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/6/98 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Injection  
~~Morrow~~ Formation Morrow Depth to Top 5746 Bottom 5770 T.D. 5860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	5746	5770	8 5/8	1530	0
				5 1/2	5860	2740

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. CIBP was set @ 5700' w/20' cmt on top prior to plugging. Circulate hole full of 9.2 ppg plug mud. Mix & pump plug #1 consisting of 50 sxs Class "C" neat cmt @ 1560'. Displace w/9.2 ppg plug mud. Set 40 sxs cmt plug from 368' to 500' (132'). Displace with 9.2 ppg plug mud. Set 10 sxs 40' cmt plug from 40' to 0'. Cut off casing head and weld on ID plate.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P. O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Debbie Kerr  
9400 N. Broadway, Suite 700

(Address) Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 21st day of September, 19 98

Patricia K. Brady  
 Notary Public

My Commission Expires: April 18, 1999

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
 KANSAS CORP.  
 998 SEP 23 1998