

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. - 82-3-117

API NUMBER 15-119-20, 123-0001

LEASE NAME Angell Unit WSW

WELL NUMBER 1

677 Ft. from S Section Line

2176 Ft. from E Section Line

SEC. 6 TWP. 33S RGE. 29 WEST (W)

COUNTY Meade

Date Well Completed 11/29/1995
12/11/92

Plugging Commenced 9/17/98

Plugging Completed 9/22/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Samedan Oil Corporation

9400 N. Broadway, Suite 700

ADDRESS Oklahoma City, Oklahoma 73114

PHONE# (405) 475-2000 OPERATORS LICENSE NO. 04570

Character of Well Water Supply Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/6/98 (date)

by Steve Durant (KCC District Agent's Name)

is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Shawnee Depth to Top 3515 Bottom 3620 T.O. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shawnee	Water	3515	3620	8 5/8"	1522	0
				5 1/2"	4057	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Set 25 sxs Class C cmt and 100# cotton seed hulls plug from 3400' to 3670'. Displace w/9.2 ppg plug mud. Set 50 sxs Class C cement plug from 1564' - 1400'. Set 40 sxs Class C cement plug from 500' to 368'. Load hole with 9.2 ppg plug mud. Set 10 sxs Class C cement plug from 40' to surface. Cut off wellhead and weld on ID plate.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P. O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Samedan Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Debbie Kerr (Employee of Operator) or (Operator) o


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Debbie Kerr

(Address) 9400 N. Broadway, Suite 700
Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 98

Susan D. Crossdale
Notary Public



USE ONLY ONE SIDE OF EACH FORM