

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,740-0000

LEASE NAME Fink

WELL NUMBER #1-7

SPOT LOCATION C NE SW

SEC. 7 TWP. 33S RGE. 29W (E) (W)

COUNTY Meade

Date Well Completed 1-24-86

Plugging Commenced 1-24-86

Plugging Completed 1-24-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Drilling & Exploration, Inc.

ADDRESS P.O. Box 1609, Great Bend, Kansas 67530

PHONE # (316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 5892'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1518	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug @ 1530' w/ 80 sx, 2nd plug @ 600' w/ 50 sx, 3rd plug @ 40' w/ 10 sx, rathole 15 sx; 155 sx 60/40 poz, 6% gel, plug down @ 5:00 a.m. 1-24-86.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc. License No. 5652

Address P.O. Box 1609, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1986


CONSERVATION DIVISION

Bill Nelson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Nelson

Bill Nelson

(Address) P.O. Box 1609, Great Bend, KS



SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 86

Pamela K. Walters
Notary Public

Pamela K. Walters

My Commission expires: August 25, 1987

Mustang Drilling & Exploration, Inc.
Fink #1-7
Meade County, Kansas

DRILLERS LOG

Sand	0	640
Sand, clay	640	1521
Shale, clay	1521	1584
Shale	1584	2780
Shale, lime	2780	3595
Lime, shale	3595	5892
RTD		5892

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1986
CONSERVATION DIVISION