

15-175-10085-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Wheatly

WELL NUMBER B-1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

C SW SW  
SEC. 24 TWP. 33S RGE. 31W (E) or (W)

COUNTY Seward

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-12-87

Plugging Completed 1-15-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center Wichita, Kansas 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5963'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1242'	none
				4-1/2"	5776'	2420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 5720' and 4 sacks cement, Shot pipe @5013', 3817', 3020', 2521', 2420', pulled a total of 77 joints of 4-1/2" casing. Plugged surface with 3 hulls, 35 gel, 60 cement, 10 gel, 160 cement, 60/40 pos, 6% gel. 1-21-87 Cement down 120', capped with 3 yards of redi-mix. Plugging Complete  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 87

James Hoover  
Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION

JAN 23 1987 Revised 07-86

CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4

Wheatley #1  
Panhandle Development Company, Inc.  
Section 24-33-31w  
Seward County, Kansas

CASING RECORD:

Commenced: 4-21-60  
Completed: 4-15-60

Ran 29 joints, new 24# J-55, 8 5/8"  
Casing, set at 1241.97' GL.  
Cemented with 400 sax Poz Mix, 2% CC  
and 2% gel and 200 sax HA-5. Cement  
Circulated. Ran 86 joints used 4 1/2"  
4.5# (2689.50) and 98 joints of new  
4.5# (3105.50), set @ 5776 KB. Cem-  
ented with 100 sax lite wite and 50  
sax common.

FORMATION

	FROM	TO	
Surface Soil and Sand	0	100	
Sand and Clay	100	340	
Red Bed and Shale	340	935	
Shale and Shells	935	1257	
Shale and Lime	1257	2555	
Lime and Anhydrite	2555	2630	
Shale and Lime	2630	2885	
Lime	2885	2975	
Lime and Shale	2975	3066	
Lime	3066	3340	
Lime and Shale	3340	3481	
Lime	3481	3730	
Lime and Shale	3730	3829	
Lime	3829	4090	
Lime and Shale	4090	4300	
Lime	4300	5741	
Lime and Shale	5741	5924	
Lime	5924	5963	RTD

STATE OF KANSAS }  
COUNTY OF SEWARD } SS

I Heroby affirm that the above and foregoing is a true and correct copy of the log of the Wheatley #1 - "B" well, located C-SW-SW of Section 24-33-31w, Seward County, Kansas.

GEO. B. McCLELLAN DRILLING ACCOUNT

*[Signature]*  
C. V. McClellan, Manager



Subscribed and sworn to before me a notary public this 16th day of April, 1960.

STATE CORPORATION COMMISSION

DEC 2 1966

*[Signature]*  
Sharon K. Halbrook, Notary Public

My Commission Expires:  
September 26, 1965