

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

SEWARD County, Sec. 25 Twp. 33 Rge. 31 (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Wm. Gruenerwald & Associates

Lease Name Sleeper Well No. 1

Office Address Box 909 Colorado Springs, Colo.

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed 3-15 1962

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced September 13 1967

Plugging completed September 16 1967

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation MORAN Depth to top 5642 Bottom 5675 Total Depth of Well 6144 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mix 15 sks. cement and 1 sk. hulls to plug off perforations. Stop plug at 5,900'. Shoot pipe at 4,023' with no results. Shoot at 3,211' - 3,014' - 2,912' - 2,709' - and loose at 2,612'. Lay down all casing, 81 jnts. in all. Pump 40 sks. cement at 700' to 575'. Fill with mud to 45'. Put 15 sks. cement at 45' to 0'.

STATE CORPORATION COMMISSION
WICHITA, KANSAS

SEP 28 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address Box 506, Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward, ss.

Wm. Gruenerwald & Associates (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Wm. Gruenerwald & Associates

(Signature) By, [Signature]
Supt.

SUBSCRIBED AND SWORN TO before me this 16th day of Sept., 1967

(Address) [Signature]
Notary Public.

My commission expires April 16, 1971



15-175-10042-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WM. GRUENERWALD & ASSOC.

SEC. 25 T. 33 R. 31W

FARM Sleeper

NO. 1

LOG. C NW SE

TOTAL DEPTH: 6144'

COUNTY Seward

COMM: 12-27-61

COMP. 4-6-62

SHOT OR TREATED

CONTRACTOR Moran Bros.

ISSUED 12-3-66



CASING:

| | | |
|----|-------|-------|
| 20 | 10 | |
| 15 | 8 5/8 | 1584' |
| 12 | 6 | |
| 13 | 4 | 6141' |

ELEVATION 2731' RB

PRODUCTION 4315 MCFGPD,
THRU SEP 350# BP:
5642075 Morr & 6065
St. Lou

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVIAIABLE.

| TOPS: SCOUT | ELEC |
|---------------|------|
| Tornoto | 4362 |
| Lansing | 4468 |
| Marmaton | 5114 |
| Cherokee | 5280 |
| Morrow | 5609 |
| Morrow Sand | 5642 |
| Chester | 5687 |
| St. Genevieve | 5896 |
| St. Louis | 6049 |

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1967

CONSERVATION DIVISION
Wichita, Kansas