

LEASE NAME Roy C. Carter "A"  
WELL NUMBER 1  
SPOT LOCATION C SW/4 NW/4  
SEC. 25 TWP. 33 SRGE. 31 W  
COUNTY Seward  
Date Well Completed 9-28-60  
Plugging Commenced 12-23-86  
Plugging Completed 01-06-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Diamond Shamrock Exploration Company  
ADDRESS P. O. Box 400, Amarillo, TX 79188-0001

PHONE (806) 378-4154 OPERATORS LICENSE NO. 9123

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Morrow & St. Louis Depth to top 5512' bottom 5530' T.D. 5903'  
5837' 5851'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	1561	10 3/4"	1561'	-0-
		Surface	5903	7"	5903'	2606'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set CIBP @ 5525' with 3. sx cmt on top, 1st plug: Pump 50 sx cls. "H" cmt from 1590'-1540'; 2nd plug: Pump 20 sx cls "H" from 750'-725'; 3rd plug: Pump 10 sx cls "H" from 20'-3'. CIBP set @ 5710' with 3 sx cmt on top

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents, Casing Pullers License No. 6547  
Address 620 South Lincoln  
Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter, ss.

Carl Burgman (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl A. Burgman  
(Address) P. O. Box 400 Amarillo, TX

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1987

Patti Jones  
Notary Public Patti Jones

My Commission expires: 5-6-89

# WELEX



## GUARD LOG

15-175-10101-0000

COMPANY \_\_\_\_\_  
 WELL \_\_\_\_\_  
 FIELD \_\_\_\_\_  
 County \_\_\_\_\_  
 State \_\_\_\_\_  
 File \_\_\_\_\_

COMPANY Shamrock Oil & Gas Company  
 WELL Roy C. Carter "A" No. I  
 FIELD S. Kismet  
 COUNTY Seward STATE Kansas

Location 1980' FNL @ 660' FWL

Other Logs  
G-N/G  
FORxo

Sec. 25 Twp 33N Rge 31W

Elevation  
 KB. 2736  
 DF. 2734  
 GL. 2726

Permanent Datum Ground Level Elev. 2726  
 Log Measured From Kelly Bushing  
 Drilling Measured From Kelly Bushing

Run No. one  
 Date 8-24-60  
 Total Depth Driller 5903  
 Total Depth Welex 5904  
 Csg. Shoe Driller 1561  
 Csg. Shoe Welex \_\_\_\_\_  
 Survey Begins 5899  
 Survey Ends 2500  
 Csg. Size 10 3/4  
 Bit Size 8 3/4

*Cement*

Mud Data - Type Starch Gel

Weight 9.3  
 Viscosity 62  
 Ph. 9.0 @ °F @ °F @ °F @  
 Wtr. Loss cc/ min... 12.6 @ °F @ °F @ °F @  
 Res. @ Surface Temp... .65 @ 82 °F @ °F @ °F @  
 Res. @ Max. Hole Temp... .99 @ 126 °F @ °F @ °F @  
 Rmf. Corrected to BHT .33 @ 126 °F @ °F @ °F @  
 Rmc. .64 @ 126 °F @ °F @ °F @  
 Source Mud Sample Flow Line NOV 17 1960  
 Recorded By B. Wright  
 Witnessed By Mr. Baker  
 Logging Tool No. 6024