

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-175-10067-0000

API NUMBER \_\_\_\_\_

LEASE NAME Frederick

WELL NUMBER 4

660 Ft. from N Section Line

1980 Ft. from E Section Line  
C NW NE

SEC. 26 TWP. 33 RGE. 31W (E) or (W)

COUNTY Seward

Date Well Completed 4-28-61

Plugging Commenced 6-29-93

Plugging Completed 7-2-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS Rt. 1 Box 56 Great Bend, Ks. 67530

PHONE# (316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Dick Kapp (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 5900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1246'	None
				5-1/2"	5895'	1500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 5850' and 5 sacks cement. Shot pipe @2000', 1700', 1500', pulled to 1246' and pumped 50 sacks cement, pulled to 700' and pumped 40 sacks cement, pulled to 40' and circulated cement to surface, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July STATE OF KANSAS REPRODUCTION COMMISSION

James Herzberg  
Notary Public **JUL 9 1993**

My Commission Expires: \_\_\_\_\_



CONSERVATION DIVISION  
Wichita, Kansas  
Revised 05/80