


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Seward County, Sec 26 Twp 33S Rge. 31 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines SE SW  
Lease Owner A. L. Abercrombie, Inc.  
Lease Name Frederick Well No. 6  
Office Address 801 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Nov. 1 1973  
Application for plugging approved Nov. 2 1973  
Plugging commenced 2-16 1974  
Plugging completed 2-19 1974  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5925 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1242	none
				5 1/2	5924	2600

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 20 sks. of cement @ 5550  
Pump 35 sks. of cement @ 800 to 700  
Put 15 sks. of cement @ 45 to 0

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1974

CONSERVATION DIVISION  
Wichita, Kansas  
RECEIVED  
STATE CORPORATION COMMISSION  
MAR 19 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511  
Address Box 506 Liberal, Kansas 67901

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1974

My commission expires 2-10-74  
Sincerely, Thann  
Notary Public.

FREDERICK NO. 6  
Panhandle Development Company, Inc.  
Section 26-33-31  
Seward County, Kansas

CASING RECORD:

Ran 41 joints of 24# 8 5/8" casing, set at 1242.13 G.L., cemented with 650 sacks HA-5; ran 189 joints of 5 1/2" casing, set at 5924', cemented bottom stage with 650 sacks lite wate, with 1/4# to 1 sack Flo Seal, and 25 sacks common 2% Gel; Cemented top stage with 100 sacks lite wate with 1/4# to 1 sack Flo Seal, and 35 sacks common, 2% Gel.

Commenced: 2-10-62  
Completed: 3-02-62

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1973  
CONSERVATION DIVISION  
Wichita, Kansas

FORMATION


	<u>FROM</u>	<u>TO</u>	
Surface Clay and Sand	0	107	
Clay and Sand	107	280	
Sand	280	520	
Red Bed and Sand	520	940	
Red Bed and Shale	940	1253	
Red Bed	1253	1315	
Red Bed and Anhydrite	1315	1810	
Anhydrite and Shale	1810	2135	
Shale and Lime	2135	2871	
Lime	2871	2965	
Lime and Shale	2965	3240	
Lime	3240	3735	
Lime and Shale	3735	3820	
Lime	3820	3910	
Lime and Shale	3910	4100	
Lime	4100	4248	
Lime and Shale	4248	4307	
Lime	4307	5925	RTD

State of Kansas )  
County of Seward ) SS

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Frederick #6 well, located C-SE-SW of Section 26-33-31, Seward County Kansas.

McCLELLAN DRILLING COMPANY

*[Signature]*  
Manager



Subscribed and sworn to before me a notary public this 5th day of March, 1962.

*[Signature]*  
Notary Public

My Commission Expires September 26, 1965.