


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner

County. Sec. 23 Twp. 30S Rge. 2 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner Beardmore Drilling Company

Lease Name Lee 'A'

Well No. 1

Office Address 827 Beacon Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-6 19 61

Application for plugging filed 3-6 19 61

Application for plugging approved 3-6 19 61

Plugging commenced 3-6 19 61

Plugging completed 3-6 19 61

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie

Producing formation Depth to top Bottom Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil, Shale, and Lime		0	200'	13 3/8"	200'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

0 to 20 - 10 sacks cement

20' - Wood plug

20 to 140' - Heavy Mud

140' to 180' - 30 sacks cement

180' - Wood plug

180' to 3830' - Heavy Mud

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1961

CONSERVATION DIVISION
Wichita, Kansas

Also: 2 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company, Inc.

Address 514 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore

(employee or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Heber Beardmore

827 Beacon Building, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 61

My commission expires March 28, 1964.

Dolores L. Curtis
Dolores L. Curtis

Notary Public.

GABBERT-JONES DRILLING CO., INC.WICHITA, KANSASDRILLER'S WELL LOG

LEE "A" #1
NE NW NE SECTION 23-30S-2W
SUMNER COUNTY, KANSAS

COMMENCED: FEBRUARY 20, 1961
COMPLETED: MARCH 6, 1961

OPERATOR - BEARDMORE DRILLING COMPANY

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	200	SHALE & SHELLS	RAN 200' OF 13-3/8" CASING, CEMENTED @ 200' W/220 SACKS CEMENT.
200	495	SHALE & SHELLS	
495	620	LIME & SHALE	
620	650	ANHYDRITE	
650	1025	LIME & SHALE	
1025	1060	LIME & CHERT	
1060	2845	SHALE & LIME	
2845	2910	SAND	
2910	2940	LIME & SHALE	
2940	3020	SHALE & PYRITE	
3020	3198	LIME & SHALE	
3198	3240	LIME	
3240	3315	LIME & SHALE	
3315	3370	LIME	
3370	3757	LIME & SHALE	
3757	3777	CORE #1	
3777	3802	CORE #2	
3802	3830	LIME	
3830	TD		DRY AND ABANDONED

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1961

CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE WELL DRILLED IN NW NW NE SECTION 23-30S-2W, SUMNER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 7TH DAY OF MARCH, 1961, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963