

15-191-20082-0008


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sumner County, Sec. 20 Twp. 30 Rge. 2 W (E) W (W)
Location as "NE/CNWSW" or footage from lines NE NE NE
Lease Owner Hummon Oil Inc.
Lease Name Armstrong Well No. # 2
Office Address 821 Union Nat'l Bldg.; Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed October 1971
Application for plugging approved October 1971
Plugging commenced October 27 1971
Plugging completed November 2 1971
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3752 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251	None
				5 1/2"	3740	2521

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

October 27, 1971 Plugged off bottom. Dumped sand to 3075'. Mixed and dumped 5 sx of cement to 3035'.
November 2, 1971 Plugged off top. Set 10' rock bridge at 260'. Mixed and dumped 20 sx of cement, mudded casing to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx of cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. BOX 1082 ; GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. E. Leith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Leith
6409 E. 14th St. WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of December 1971
Scharla L. Herrington
Scharla L. Herrington Notary Public.

My commission expires May 1, 1974

R

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1971

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG
Armstrong #2
NE NE NE 20-30S-2W
Sumner County, Kansas

Company: WILLIAM OIL CO.
Address: WICHITA, KANSAS
Phone: 373-1111
County: SUMNER

WELL BASE INFO: NE NE NE 20-30S-2W

DEPTH	FROM	TO	DESCRIPTION	Elevation: 1354 K.B.
	0	140	Red Bed and shale	
	140	258	Red Bed and shells	
	258	1000	Shale and lime	
	1000	1330	Lime and shale	
	1330	2700	Shale and lime	Lm, dense
	2700	3015	Lime and sand	Sh, lm saks
	3015	3115	Shale	Lm, dense scatt vugs
	3115	3752	Lime	Lm, sl/vuggy, vert fr
1	3752	3752	Total Depth	60.0
2				55.7
3				52.7
4				44.1
5	09-10			41.5
6	10-11			36.3
7	11-12			31.0
8	12-13			27.6
	13-14			
	3114-15			

STATE OF KANSAS


COUNTY OF BARTON ss

T. D. Sweetman, President of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

T. D. Sweetman
T. D. Sweetman

Subscribed and sworn before me this 13th day of August, 1968.

Leata L. Boyd
Notary Public Barton County



This report was prepared on observations and materials supplied by the client to whom, and for whose exclusive and confidential use, it is intended. The opinions expressed represent the best judgment of Core Laboratories, Inc. (all errors and omissions excepted); but Core Laboratories, Inc. and its employees, assume no responsibility and make no warranty or representations, as to the productivity, proper operations, or other mineral well or sand in connection with which such report is used or relied upon.