


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Meade County. Sec. 16 Twp. 33S Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Texaco Inc.
Lease Name Emma McJones Well No. 1
Office Address 614 Bitting Bldg, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Gas Well
Date well completed 5-12- 1956
Application for plugging filed 2-1- 1966
Application for plugging approved 2-2- 1966
Plugging commenced 2-15- 1966
Plugging completed 2-27- 1966
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production November 1963
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublett, Kansas
Producing formation Morrow Depth to top 5758 Bottom 5766 Total Depth of Well 5872 Feet
Show depth and thickness of all water, oil and gas formations. PBTB 5799

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|------|---------|--------|------------|
| Morrow | Gas | 5758 | 5766 | 16" | 209' | None |
| | | | | 10-3/4" | 1500' | None |
| | | | | 7" | 5875' | 3050' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: 5799-5661' w/25 sxs cmt.,
5661-700' w/hvy drlg mud,
700-600' w/50 sxs cmt.,
600-40' w/hvy drlg mud.,
40-surface w/20 sxs cmt.
Complete 4 PM 2-26-66.

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Service
Address Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. R. Wilson (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson
614 Bitting Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 1966

My commission expires 10-13-69

Notary Public.

DRILLING LOG

The Texas Company - Emma McDones Well No. 1, located in Sec. 15,
Twp 33-S., Rge 29-W., Meade County, Kansas.

Started: 3-23-56

Completed: 4-21-56

Casing: 16" Set at 207' W/250 Sax at 10:00 A.M.
 3-24-56 - W.O.C. 26 1/2 Hrs
 10 3/4" set at 1502' W/1000 Sax at 9:45 PM
 3-26-56 W.O.C. 29 1/4 Hrs
 7" Set at 5871' W/250 Sax at 11:30 PM
 4-20-56 W.O.C. 20 1/2 Hrs

- 0 - 212 Sand & Clay
- 212 - 1311 Red Beds & Sand
- 1311 - 1502 Red Beds
- 1502 - 1699 Anhydrite
- 1699 - 2317 Red Beds
- 2317 - 2470 Shale
- 2470 - 2515 Lime & Shale
- 2515 - 2750 Lime & Anhydrite
- 2756 - 2935 Lime & Shale
- 2935 - 3037 Lime
- 3037 - 5700 Lime & shale
- 5700 - 5871 T.D. (Cored)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 2 1966
 CONSERVATION DIVISION
 Wichita, Kansas