

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Meade

County, Sec. 16 Twp. 33S Rge. 29W (E) (W)

Location as "NE/CNW/SW" or footage from lines Center SW/4 NW/4

Lease Owner The Texas Company

Lease Name V. R. Cottrell Well No. 1

Office Address 614 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed July 16 19 57

Application for plugging filed July 19 19 57

Application for plugging approved July 22 19 57

Plugging commenced July 29 19 57

Plugging completed August 1 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 5952 Feet

Show depth and thickness of all water, oil and gas formations. PBD 5884

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 1547   | None       |
|           |         |      |    | 5-1/2" | 5954'  | 4660'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5884' to 5800' - Sand  
 5800' to 5775' - 5 Sacks Cement  
 5775' to 450' - Heavy Mud  
 450' to 440' - Rock Bridge  
 440' to 380' - 20 Sacks Cement  
 380' to 35' - Heavy Mud  
 35' to 30' - Rock Bridge  
 30' to surface - 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & S Pipe Pulling Company  
Address Box 192, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Gene R. Bates (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gene R. Bates  
614 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 57

My commission expires September 20, 1960

Howard Kistler  
Notary Public  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC. 16 T. 33R. 29W  
BOOK PAGE 29 LINE 16

AUG 27 1957  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLING LOG

The Texas Company - V. R. Cottrell No. 1 Well, Sec. 16, Twp 33 So.,  
Rge 29 W., Meade County, Kansas.

Started: 6-5-57  
Completed: 7-5-57  
Casing: Set 8 5/8" at 1541' W/650 Sax Pozmix  
& 100 Sax Regular at 1:30 AM 6-7-57  
W O C 24 Hours  
Set 5 1/2" at 5951' W/200 Sax Pozmix &  
50 Sax Common at 5:30 PM 7-3-57  
W O C 6 1/2 Hrs

- 0 - 518 Sand
- 518 - 1144 Red beds, Sand & shale
- 1144 - 1541 Red beds & sand
- 1541 - 2392 Red Beds & shale
- 2392 - 2521 Shale & lime
- 2521 - 2668 Lime & shale
- 2668 - 2748 Lime
- 2748 - 2910 Lime & shale
- 2910 - 3020 Lime
- 3020 - 3200 Lime & shale
- 3200 - 3255 Lime
- 3255 - 3420 Lime & shale
- 3420 - 3583 Lime
- 3583 - 3805 Lime & shale
- 5805 - 5846 (Cored)
- 5846 - 5875 (Not shown)
- 5875 - 5952 T.D. (Cored)

tops

- Lansing 4619
- Marmaton 5268
- Cherokee 5452
- Atoka 5596
- Morrow 5762
- Morrow Sand 5812
- Mississippi 5898

|                 |      |               |         |
|-----------------|------|---------------|---------|
| <b>PLUGGING</b> |      |               |         |
| FILE            | SEC  | 16 T 33 R 29W |         |
| BOOK            | PAGE | 29            | LINE 16 |

RECEIVED  
STATE CORPORATION COMMISSION

AUG 27 1957

CONSERVATION DIVISION  
Wichita, Kansas

