


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

MEADE County. Sec. 18 Twp. 33S Rge. 29W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SE SW

Lease Owner George R. Jones
Lease Name BURMEISTER Well No. 1
Office Address Suite 1310, 125 No. Market, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plot

Date Well completed December 28, 1978 19
Application for plugging filed 19
Application for plugging approved Jan. 3, 1979 19
Plugging commenced December 28, 1978 19
Plugging completed December 28, 1978 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation none Depth to top - Bottom - Total Depth of Well 5890
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----------|----------------|-----------------|--------------|
| | | | Ran 38 | jts of 23# | 8-5/8" csg | set at 1537' |
| | | | | cemented w/600 | sk L.W. 4% GeI. | 2% CC + |
| | | | 200 | sk Common 3% | CC PD @ | 12:15 p.m. |
| | | | 12-13-78 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
11:00-6:45 GIH lay down D.C. GIH lay down D.P. set 60 sks common - plug @ 1500' 10 sks 0-40' J. C. @ 6:45 a.m. rig down.

RECEIVED
STATE CORPORATION COMMISSION

JAN - 9 1979

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
George R. Jones (employee of owner) or (owner of operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones
Suite 1310, 125 No. Market, Wichita, Ks 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 79

Wilma E. Clark
Wilma E. Clark Notary Public.

My commission expires August 5, 1980



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Burmeister #1
SE SW/4 Sec 18-33S-29W
Meade County Kansas

Commenced: 12-12-78

Completed: 12-28-78

OPERATOR: George Jones

| Depth | | Formation | Remarks |
|-------|-----------|----------------------|---|
| From | to | | |
| 0 | 1011 | Surface Sand-Redbed | Ran 38 jts of 23 8 5/8" csg set @ 1537' Cemented w/ 600 sks L.W. 4% Gel 2% CC + 200 sks Common 3% CC PD @ 12:15 p.m. 12-13-78 |
| 1011 | 1540 | Sand-Redbed | |
| 1540 | 1630 | Redbed-Sand-Anhy | |
| 1630 | 1950 | Redbed-Sand | |
| 1950 | 2382 | Sand-Shale | |
| 2382 | 2426 | Shale-Salt Stringers | |
| 2426 | 2586 | Shale-Shale w/Lime | |
| 2586 | 2735 | Lime-Shale | |
| 2735 | 2900 | Shale-Lime-Dolo | |
| 2900 | 3245 | Lime-Shale | |
| 3245 | 3454 | Lime-Shale-Chalk | |
| 3454 | 5557 | Lime-Shale | |
| 5557 | 5635 | Lime | |
| 5635 | 5730 | Lime-Shale | |
| 5730 | 5776 | Shale | |
| 5776 | 5827 | Lime-Shale | |
| 5827 | 5890 | Lime | |
| | 5890 - TD | | DRY & ABANDONED |

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
Drillers' Well Log is true and correct to the best of my knowledge and belief and
according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 5th day of January, 1979.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

NOTARY PUBLIC
STATE OF KANSAS

RECEIVED
STATE CORPORATION COMMISSION

JAN - 9 1979

CONSERVATION DIVISION
Wichita, Kansas

JAN - 9 1979

CONSERVATION DIVISION
Wichita, Kansas