


15-119-10172-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Meade County, Sec. 22 Twp. 33S Rge. 29 W (W)
Location as "NE/CNW/SE" or footage from lines C SE SE
Lease Owner The Shamrock Oil and Gas Corporation
Lease Name Clarence L. Rexroad "A" Well No. 1
Office Address Box 631, Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 14 19 59
Application for plugging filed July 14 19 59
Application for plugging approved July 14 19 59
Plugging commenced July 15 19 59
Plugging completed July 15 19 59
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & clay	Water	0	300	9 5/8"	1,555	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
FILLED hole with heavy mud to 600'. Pushed 9 5/8" Halliburton plug to 600'. Spotted 35 sacks cement at 600'. Filled hole with heavy mud to 35'. Pushed 9 5/8" Halliburton plug to 35'. Filled casing from 35' to surface with 25 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Meade, Kansas

STATE OF TEXAS, COUNTY OF POTTER, ss.
T. S. Clopton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. S. Clopton
Box 631, Amarillo, Texas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 59
My commission expires 6-1-61
Potter County, Texas

PLUGGING
FILE SEC. 22 T. 33 R. 27W
BOOK PAGE 62 LINE 17

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1959
CONSERVATION DIVISION
Wichita

CLARENCE L. REXROAD "A" NO. 1
Meade County, Kansas

C SE SE 22-33S-29W

0' - 300'	Surface, sand & clay
300' - 400'	Shale & shells
400' - 560'	Red bed & shale
560' - 1,260'	Red bed & shells
1,260' - 1,505'	Red bed, shells, & anhydrite
1,505' - 1,555'	Shale with anhydrite streaks
1,555' - 1,800'	Shale & shells
1,800' - 2,080'	Shale & lime
2,080' - 2,350'	Shale & anhydrite
2,350' - 2,970'	Shale & lime
2,970' - 3,125'	Shale & lime with chalk streaks
3,125' - 3,592'	Lime & chalk
3,592' - 3,809'	Shale & lime
3,809' - 3,835'	Lime
3,835' - 3,903'	Lime & shale
3,903' - 3,970'	Lime
3,970' - 4,122'	Shale
4,122' - 4,192'	Lime
4,192' - 4,369'	Shale
4,369' - 4,611'	Lime & shale
4,611' - 5,390'	Lime
5,390' - 5,445'	Lime & shale
5,445' - 5,593'	Lime
5,593' - 5,630'	Lime & shale
5,630' - 5,655'	Shale & shaley lime
5,655' - 5,890'	Lime & shale

PLUGGING

FILE SEC. 22-33R12

BOOK PAGE LINE