

15-119-00025-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 22 Twp. 33S Rge. (K) 29 (W)

Location as "NE/CNW/SE/SW" or footage from lines. C SE NW

Lease Owner Gulf Oil Corporation

Lease Name H. C. Bender Well No. 1

Office Address 316 Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 2-18, 19 56

Application for plugging filed 8-14, 19 59

Application for plugging approved 8-17, 19 59


Plugging commenced 8-21, 19 59

Plugging completed 8-25, 19 59

Reason for abandonment of well or producing formation Well operating below its economic limit.

If a producing well is abandoned, date of last production 6-8, 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation Morrow sand Depth to top 5722' Bottom 5728' Total Depth of Well 5910 Feet

Show depth and thickness of all water, oil and gas formations. PBTB 5859'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1332'	-0-
				4-1/2"	5902'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PBTB 5859'. Filled hole with sand from 5859' to 5700'. Dumped 4 sacks cement from 5700' to 5652'. Mudded hole to 640'. Placed 10' rock bridge to 630'. Dumped 25 sacks cement to 555'. Mudded hole to 50'. Set rock bridge from 50' to 40'. Capped to top of surface pipe with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service

Address Hutchinson, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Thomas A. Trax (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas A. Trax

316 Union Center Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August 1959

My commission expires June 3, 1961

C. C. LEWIS, NOTARY PUBLIC

Notary Public.

PLUGGING
FILE SEC. 22 T. 33 R. 20W
BOOK PAGE 60 LINE 16

15-119-00025-0000

WELL LOG

COMPANY Gulf Oil Corporation

SEC. 22 T. 33S R. 29W
LOC. S1/4 NW1/4

FARM H. C. Bender

NO. 1

TOTAL DEPTH 5910'

COMM. 1-13-56

COMP. 2-8-56


COUNTY Meade

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASINO

20	10
15	8 5/8" 1332'
12	6
13	4 1/2" 5090'

ELEVATION 2548 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	235	Surface Soil & Sand
235	350	Shale & Rock
350	470	Red Bed & Shells
470	560	Shale & Soap Rock
560	690	Sand
690	815	Red Bed & Shale
815	860	Anhydrite
860	1125	Sand, Shale & Red Bed
1125	1326	Red Bed & Shale
1326	1360	Anhydrite
1360	1855	Shale & Sand
1855	1910	Anhydrite & Shells
1910	2270	Shale & Shells
2270	2335	Anhydrite
2335	2490	Anhydrite, Shale & Sand
2490	2715	Lime & Shale
2715	2875	Sand & Shale
2875	2955	Lime, Shale & Sand Stks.
2955	3220	Lime & Shale
3220	3310	Lime & Chalky Lime
3310	3550	Lime & Shale
3550	3690	Lime & Chalk, Lime & Shale
3690	3765	Chalky Lime
3765	4115	Lime & Shale
4115	4132	Shale, Lime & Shells
4132	4170	Shale & Lime
4170	4567	Lime
4567	4630	Lime & Chalky lime
4630	4680	Chalky lime & shale
4680	4750	Lime & Shale
4750	5001	Lime
5001	5095	Lime, Shale & Sand
5095	5155	Shale & Lime
5155	5335	Lime
5335	5361	Lime & Shale
5361	5410	Shale
5410	5660	Lime & Shale
5660	5758	Coning
5758	5849	Lime & Shale
5849	5880	Shale

GEOLOGIC TOPS:

Lansing K G	4518'
Skiatook	5003'
Marmaton	5174'
Cherokee	5373'
Morrow Shale	5675'
Morrow Sand	5721'
Mississippian	5804'

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1959
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedwick

PLUGGING
FILE SEC. 22 T. 33R R. 29W
BOOK PAGE 60 LINE 16

I, L. B. Bailey of the County of Sedwick State of Kansas do hereby certify that the above and foregoing is a true and correct copy of the log of the H. C. Bender #1 well.

Subscribed and sworn to before me this 13th day of February 19 56

My Commission Expires April 20, 1959

Walter M. Binger
NOTARY PUBLIC
(Vestanna M. Binger)