

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
207 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-10193-2000

LEASE NAME E.F. Harris

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

SW 1/4 Ft. from S Section Line

         Ft. from E Section Line

SEC. 24 TWP. 33S RGE. 29W (E) or (W)

COUNTY Meade

LEASE OPERATOR H I., Inc.

ADDRESS Box 2526 Liberal, Kansas 67905

PHONE# (316) 624-8484 OPERATORS LICENSE NO.         

Date Well Completed         

Character of Well Gas

Plugging Commenced 4-1-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-4-91

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 5850

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1330	0
				5 1/2	5830	2612

APR 26 1991

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 1 sk. of hulls & 25 sks. of cement from 5209 to 5050

Pump 50 sks. of cement from 1360 to 1260

Pump 30 sks. of cement from 700 to 600

Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506


STATE OF Kansas COUNTY OF Seward, ss.

Harold E. Box JR

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold E. Box JR

(Address) P.O. Box 2526 Liberal, Ks. 67905



AND SWORN TO before me this 25 day of April, 19 91

Terri L. Daugherty  
Notary Public

My Commission Expires: Oct. 20, 1991

15-119-10193-0006  
 DESIGNATE TYPE OF COMP.: OIL, GAS,  
 DRY HOLE, SWDW, ETC.:

Getty Oil Co.

Well No. 1	Lease Name E. F. Harris	Gas
S 24 T 33S R 29 W		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and clay	0	260		
Red bed	260	620		
Shale	620	1795		
Shale and shells	1795	1930		
Shale	1930	2240		
Shale and anhydrite	2240	2307		
Shale	2307	2470		
Lime and shale	2470	2815		
Lime	2815	2865		
Lime and shale	2865	3034		
Lime	3034	3070	Council Grove	TOPS 3038'
Lime and shale	3070	3202		
Lime	3202	3445		
Lime and shale	3445	3569		
Lime	3569	3605		
Lime and shale	3605	3725		
Lime	3725	3759		
Lime and shale	3759	3840		
Lime	3840	4040		
Lime and shale	4040	4105		
Lime	4105	4365	Heebner	4350'
Lime and shale	4365	4420		
Lime	4420	5654	Lansing Lime	4523'
Shale and sand	5654	5697	Marmaton	5148'
Lime and sand	5697	5732	Cherokee	5348'
Lime	5732	5850	Morrow	5650'
Total Depth		5850	Morrow Sand Chester	5675' 5735'

DST #1 - Morrow Sand - 5642'-5697'

Open 65 min. gas to surface in 2 min.; gauged 1,250 MCF in 3 mins. 3,500 MCF in 65 min. Rec. 80' free oil, 360' salt water. IBHP 1850#; IFP 445#; FFP 665#; FBHP 1770#.

DST #2 - Chester - 5751'-5806'

Open 60 min. gas to surface in 3 min.; gauged 196 MCF in 5 min.; 60 MCF in 1 hr. Recovered 5' gas cut drilling mud. IBHP 2000#; IFP 15#; FFP 35#; FBHP 1930#.

DST #3 - Chester - 5808'-5842'

Open 60 min. Good blow immediately, decreasing to weak blow in 25 min. and very weak blow in 50 min. Rec. 30' drilling mud. IBHP 1295#; IFP 35#; FFP 55#; FBHP 565#.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p>RECEIVED          STATE CORPORATION COMMISSION</p> <p>APR 01 1991</p> <p>CONSERVATION DIVISION          Wichita, Kansas</p>	<p><i>X. S. Tel</i>          Signature</p> <p>Adm. Supervisor          Title</p> <p>April 16, 1981          Date</p>
---------------	--	--