


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Meade County, Sec. 25 Twp. 33 Rge. 29 (E) (W) X
Location as "NE/CNW/KSW" or footage from lines SW/4 SW/4 NW/4
Lease Owner Kaiser - Francis
Lease Name Cordes Well No. 1
Office Address 4120 East 51st. Street Tulsa, Oklahoma 74135
Character of Well (completed as Oil, Gas or Dry Hole) *Oil* Gas
Date well completed _____ 19____
Application for plugging filed May 14 19 74
Application for plugging approved May 16 19 74
Plugging commenced May 21 19 74
Plugging completed May 24 19 74
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5820 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1197	none
				5 1/2	5819	2744

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 20 sks. of cement to 5540
Pump 35 sks. of cement @ 1000 to 900
Put 15 sks. of cement @ 45 to 0

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 0 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Tulsa ss.
Harry L. Berry (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry L. Berry
4120 East 51st St., Tulsa, Okla. 74135
(Address)

Subscribed AND SWORN to before me this 7th day of June, 19 74

My commission expires June 12, 1976
G. A. Weber Notary Public.

15-119-00068-0000
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas


COPY

Company- SUN OIL COMPANY
 Farm- Cordes No. 1

SEC. 25 T. 33 R.29W
 SW SW NW

Total Depth. 5824'
 Comm. 6-9-58 Comp. 7-18-58
 Shot or Treated.
 Contractor. Falcon - Seaboard Drlg. Co.
 Issued. 11-29-58

County Meade KANSAS



Elevation. 2456 DF

Production. 11,000,000 CFG
 CAL OPEN FLO

CASING:

13 5/8" 119' w/200 sx. cem.
 8 5/8" 1497' w/800 sx. cem.
 5 1/2" 5819' w/200 sx. cem.

Figures Indicate Bottom of Formations.

SAND	100
shale	121
sand, shale red beds	518
red bed & anhydrite	1015
shale, red bed and sand	1386
shale and anhydrite	1510
shale	1780
lime and shale	1910
lime	2575
lime and shale	3175
lime w/shale streaks	3570
limey shale	3725
lime and shale	3838
shale	3870
lime and shale	4000
shale	4070
lime and shale	4110
lime	4140
shale	4288
lime and shale	4324
Heebner shale	4368
lime and shale	4481
Lansing Lime	5122
Marmaton Lime	5334
Cherokee Shale	5356
Ls. w/streaks shale	5633
Morrow shale	5655
Morrow Sand	5680 (DST flowed 11,400 MCF/D)
shale	5725
Chester Lime	5824
Total Depth	
TOPS SCOUT	
Lansing	4474
Marmaton	5121
Morrow Sand	5655
Mississippian	5724

RECEIVED
 STATE CORPORATION COMMISSION

MAY 28 1974

CONSERVATION DIVISION
 Wichita, Kansas