

15-1291-10550-00 00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 12/5/58 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549 8-01

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Taloga Mor "G" WELL NO. 304 WELL LOCATION C NE NW COUNTY Morton

SEC. 35 TWP. 34S RGE. 42 (E or W) TOTAL DEPTH 4625 PLUG BACK TD 4582

Check One:

OIL WELL GAS WELL D & A SWD or INF WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1433 CEMENTED WITH 800 SACKS

CASING SIZE 5-1/2" SET AT 4624 CEMENTED WITH 175 SACKS

PERFORATED AT 4529-41'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH w/2-3/8" workstring. Circ hole w/9 ppg dm. Spot 5 sxs on top of CIBP @ 4509'. TOH w/workstring. Shoot csg off @ free point. Spot 40 sxs @ cut off 60 sxs @ 1533-1333', 30 sxs @ 650-550' & 15 sxs @ 50-3'. Cut: off 8-5/8" csg 3' below ground
(If additional space is needed use back of form.) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? Filed
(If not explain.) Drillers I

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon KCC Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE # (316) 697-2188

ADDRESS P.O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547 6-82

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED
STATE CORPORATION COMMISSION

SIGNED: J. L. Ashton
(Operator or Agent) J. L. Ashton
Division Production Mgr.

DATE: 7/19/91

III 2.2 1991

CONSERVATION DIVISION
Wichita, Kansas

①

Joan Finney
Governor

Jim Robinson
Chairman

Keith R. Henley
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian J. Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 23, 1991

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67905-0351

Taloga Mor G 304
C NE NW
Sec. 35-34-42W
Morton County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760