

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-129-20766-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549 8/90

ADDRESS P.O. Box 351, Liberal, KS 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Watson "B" WELL NO. 1 WELL LOCATION 100' S of C W/2 COUNTY Morton

SEC. 35 TWP. 34S RGE. 42 (R) or (W) TOTAL DEPTH 4906 PLUG BACK TD 4906

Check One:

OIL WELL ___ GAS WELL ___ D & A X SWD or INJ WELL ___ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1366 CEMENTED WITH 675 SACKS

CASING SIZE 5 1/2" SET AT 4700 CEMENTED WITH 200 SACKS

PERFORATED AT 4574-80, Squeezed with 100 sacks, 4490 squeezed with 150 sacks (over)

CONDITION OF WELL: GOOD X POOR ___ CASING LEAK ___ JUNK IN HOLE ___

PROPOSED METHOD OF PLUGGING (1) TIH W/1 1/2" tubing to 4906, load hole w/36 Vis Mud.

(2) Spot 60 sx's cement at 4906, (ETOC 4400'). (3) TOH w/tbg. (4) Pull casing stretch

test & locate free-point. (5) Shoot off casing @ free-point & retrieve pipe. (over)

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? *No ___ IS ACO-1 FILED? Yes

(If not explain.) *Logs on file w/ACO-1.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon KCC approval.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. **READ THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: **STATE RECEIVED**

Marvin B. Johnson PHONE # (316) 697-2188 **OCT 25 1989**

ADDRESS Drawer X, Elkhart, Kansas 67950 **CONSERVATION DIVISION**
Wichita, Kansas

PLUGGING CONTRACTOR Sargent's Casing Pullers Service LICENSE NO. 6547 6/90

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: [Signature]
(Operator or Agent)

DATE: 10/20/89

①

Perforations (continued)

4508-4546, squeezed with 50 sacks. Well was deepened to St. Louis. Open hole from 4700-4906.

(6) TIH w/tbg & spot cement plug 100' below to 100' above casing cut-off point (50 sxs). (7) Spot cement plug 100' above & 100' below surface casing shoe @ 1366' (50 sxs). (8) Spot cement plug from 53'-3' (15 sxs). (9) Cut-off casing 3' below ground-level and weld on cap. (10) Restore location.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
JAN 27 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

October 27, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351

Watson "B" 1
100' S of C W/2
35-34-42W
Morton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS. 67801
(316) 225-6760