

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of J.M. Huber has this

date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: J.M. Huber Corporation

Complete Address: Box 831, Borger, Texas

Lease Name: Lemon Well No. 1

Location: SW SW NE Sec. 31 Twp. 32 Rge. 40 (E) (W)

County: Morton Total Depth 5605' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 2478' circulated w/ cement. 13 3/8" to 520' circulated w/ cement.

Plug back T.D. 2410' Top perforations 2308'

Plug bottom w/10 sacks cement Top of cement 2192'

Mud 2192' to 660' Spot 40 sacks cement 660' to 480'

Mud 480' to 30' Plug, Halls & 10 sacks cement 30' to 0'.

Weld Plate on 8/8/ 13 3/8".

Very truly yours,

Edgar J. Eves
Conservation Division Agent