

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
JUN 13 1969  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of D.J. Stone has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: D.J. Stone

Complete Address: 217 Town & Country Village, Palo Atlo, Calif.

Lease Name: Clabidge Well No. 1

Location: C SE Sec. 4 Twp. 32 Rge. 41 (E) (W)

County Morton Total Depth 5385' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1491' circulated w/ cement. 5 1/2" to 5381' cemented.

Top perforations 5212' Plug bottom w/ 20 sacks cement

Top of cement 5000' ~~Spot~~ Mud 5000' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hills & 15 sacks cement 45' to 0'.

Very truly yours,

*Edward J. Evers*  
Conservation Division Agent